

**TOWNSHIP OF WELLINGTON NORTH
FERGUS STREET RECONSTRUCTION
PROJECT NO. 21340,1; CONTRACT NO. RFT-2024-005**

ADDENDUM NO. 1

Plan takers shall note the following:

(1) Revisions to Schedule of Items and Prices

The Contractor shall note revisions to the Schedule of Items and Prices as described below and as contained in the attached page T-2 (Revised). The revised page shall be used in the tender submission. The changes from the original are as follows:

- Fix minor spelling error in title
- Item 1 sub-items re-lettered to a) through e)
- Item 1 sub-item “Contractor’s Qualified Person (QP) for O. Reg. 406/19 related tasks” has been changed to **Provisional**

(2) Construction Start Date

The Contractor shall note that Enbridge is scheduled to complete relocation of the gas line on the east side of the street from its current location to approximately 0.6m off of east property line. Enbridge’s contractor is scheduled to begin this work in April, and it must be completed before the Township’s Contractor begins construction. To accommodate this schedule, **the Contractor shall note that construction is not permitted to begin until May 21, 2024.**

(3) Watermain Items

The Contractor shall note the following requirements related to proposed watermain:

- The Township of Wellington requires watermains to be disinfected using the “Continuous Feed” method of chlorination.
- The pressure rating of restraint systems shall be a minimum of 235 psi (1620 kPa) as opposed to the 350 psi indicated on page SP-39.

(4) Use of #116 Baptist Church as School

The Contractor shall note that the Church at #116 is currently being used as a temporary school location due to the recent fire at St. Marys Catholic School. To accommodate busing, the Contractor shall note that the Fergus/Wellington intersection shall remain open at all times during construction unless otherwise approved in writing by the Township.

(5) **Structure lids/grates**

- Structure #54 grate shall be changed to a MH frame and cover, OPSD 401.010A.
- Structure #55 frame and cover shall be changed to OPSD 401.010A

(6) **MH Pipe Adapters**

The Contractor shall note that the Township requires “Kor-N-Seal” pipe adaptors for all pipe connections at sanitary MHs and requires them for storm MHs where SDR-35 PVC pipe is being connected. The Contractor shall provide these pipe adaptors where applicable, based on the above requirements.

B. M. ROSS AND ASSOCIATES LIMITED
Engineers and Planners
206 Industrial Drive, Box 1179
Mount Forest, ON N0G 2L0
Phone: (519) 323-2945
www.bmross.net

March 5, 2024

(Bidders are reminded that they must acknowledge the correct number of addenda issued on page T-1 of the tender submission document.)

THE AFORESAID SUM IS MADE UP AS FOLLOWS:

SCHEDULE OF ITEMS AND PRICES

Item	Spec. #	Description	Qty. / Unit	Price	Amount
<u>PART 1 - FERGUS STREET RECONSTRUCTION</u>					
<u>ROADWORK</u>					
1	206, SP	Earth excavation and management of excess soils			
	a)	Salt impacted soil (all other concentrations below Table 2.1 ESQS) - Estimated quantity = 2100 m ³	1 L.S.	\$_____	
	b)	Remove and dispose of existing roadway asphalt between existing sidewalks on Fergus Street	2160 m ²	\$_____	\$_____
	c)	Remove and dispose of existing asphalt on Birmingham Street indicated on drawings (Provisional)	1 L.S.	\$_____	
	d)	Remove and dispose of existing driveway asphalt behind existing sidewalks	150 m ²	\$_____	\$_____
	e)	Contractor's Qualified Person (QP) for O. Reg. 406/19 related tasks (Provisional)	1 L.S.	\$_____	
2	501, 506, SP	Dust suppressants and compaction			
	a)	Water	130 m ³	\$_____	\$_____
	b)	Calcium chloride solid	1.3 t	\$_____	\$_____
3	314, 351, SP	Granular A	1300 t	\$_____	\$_____
4	314, SP	Granular B Type I	2400 t	\$_____	\$_____
5	310, 311, 312, SP	Hot Mix Asphalt			
	a)	Hot Mix HL-4	220 t	\$_____	\$_____